

अखिल भारतीय आयुर्विज्ञानसंस्थान, रायपुर (छत्तीसगढ़)

All India Institute of Medical Sciences, Raipur (Chhattisgarh)

Tatibandh, GE Road,
Raipur-492 099 (CG)
www.aiimsraipur.edu.in

No. **NIe/06 / SE/AIIMS/2017-18**

Date: 14/07/2017

NOTICE INVITING QUOTATIONS

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors/Firms/Individuals/Supplier having GST/TIN/PAN no./relevant documents and should be submitted to office of Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to 3:00 pm on 21th July 2017. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at 3:30 pm. As per detailed below:-

SI No	NAME OF WORK	EST. COST in	E.M.D in `	TIME
1	Making of Cupboard with Granite Top in Molecular diagnostic Lab at AIIMS Raipur.	Rs. 56,200/-	Nil	15 Days

SCHEDULE OF QUANTITY

Sl.	Description of items	Quantity Rate	Unit	Amount
.....As PER SHEET ATTACHED.....				

Conditions:

1. Rate should be quoted inclusive all taxes (Nothing to be paid extra on this account). Percentage / Quantum of Tax shall be mentioned.
2. F.O.R. Project Cell, Hospital Administrative Block, Gate No-01, AIIMS Raipur.
3. Three month warranty from the date of providing or as per manufacturer which is more & damages during transportation to be liable to contractor. 5% security deposit will be withheld from his bill and shall be released after the period of three month from the date of completion.
4. The supply will be taken as per mentioned make on schedule of quantity i.e. as per specification and direction of Engineer-in-charge.
5. Work should be completed within 15 days from the date of issue of Work order.
6. The right to reject any or all the quotations without assigning any reasons and accept full or part of Quotation thereof shall rest with undersigned.
7. List of approved material to be used in this work-
Ply Wood - Green ply, Century, Duro
Emulsion/ Synthetic Enamel Paint - Snowcem, Asian, ICI Dulux, Berger, Nerolac
High Pressure Laminates - Century, Greenlam, Duro, Archidlam

JE (C)
AIIMS Raipur

SE
AIIMS Raipur

EE (C)
AIIMS Raipur
14/7

SCHEDULE OF QUANTITY

Name of Work: Making of Cupboard with Granite Top in Molecular diagnostic Lab at AIIMS Raipur.

S no	DSR ref no	Description of item	Qty	Unit	Rate	Amount
1	9.45	Providing and fixing teak wood lipping of size 25x3 mm	60.0	mt		
2	9.79.1	Providing and fixing special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc. complete : 40 mm :	5.0	Nos		
3	9.97.5	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100x10 mm :	3.0	Nos		
4	9.114.2	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete : Double strip (horizontal type) :	3.0	Nos		
5	9.115	Providing and fixing powder coated telescopic drawer channels 300 mm long with necessary screws etc. complete as per directions of Engineerin- charge.	8.0	Sets		
6	9.127.2	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality : 1.0 mm thick :	3.86	Sqm		
7	13.62.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture :	28.29	Sqm		
8	14.53.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work :	15.00	Sqm		
9	LMR	Providing & Fixing 18 mm thick water proof (BWP phenol bonded) Ply board of approved 1st quality and manufacture Duro/century/Green in furniture work etc, complete as per the direction of Engineer in charge.	13.78	Sqm		

[Handwritten signature]
16/09


[Handwritten signature]
16/09

10	LMR	Providing & Fixing 12 mm thick water proof (BWP phenol bonded) Ply board of approved 1st quality and manufacture Duro/century/Green in furniture work etc, complete as per the direction of Engineer in charge.	5.77	Sqm		
11	LMR	Providing and fixing 75mm decorative stainless steel brush finished handle of approved make with necessary screw complete as per direction of Engineer In Charge :	14.00	Nos		
12	LMR	Providing S.S. Piano hinges and fixing with necessary screws etc., complete : Overall width 35 mm :	5.04	mt		
13	LMR	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture fixed after cutting chase in the wall and making good with cement mortar 1:4, joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels : Granite of any colour and shade : Area of slab over 0.50 sqm :	2.34	Sqm		
					Total	

Total (In Words)



(Signature of Contractor)


Executive Engineer (Civil)
Project Cell, AIIMS Raipur