



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
 Tatibandh, GE Road,
 Raipur-492 099 (CG)
www.aiimsraipur.edu.in

No. 54(8017)/SE/ AIIMS/RPR/2017 -2018 /NIQ-15

Dated:-12.10.2017

NOTICE INVITING QUOTATION

Sealed Item Rates quotations for the below mentioned work are hereby invited by the Superintending Engineer on behalf of Director AIIMS Raipur From approved and eligible Contractors/Firms/Individual/Supplier having GST No./TIN/PAN No./Relevant documents should be submitted to office of Superintending Engineer, Project Cell, Hospital Administrative Block Gate No.-1, AIIMS Raipur up to 03:00 pm on 23 October 2017, Monday. The quotation will be opened on the same day at 3.30 pm.

The right to reject of any or all the quotations without assigning any reasons thereof shall rest with undersigned. As per below work:-

Name of Work:- **Supplying ,Installation,commissioning and testing of UPS System batteries at Trauma Building AIIMS Raipur.**

SCHEDULE OF QUANTITY

Sl.	Description of items	Unit	Quantity	Rate	Amount
.....As PER SHEET ATTACHED.....					

Terms & Conditions:-

1. The rates are to be quoted in words and figures including all taxes, octroi, transportation etc for all items.
2. The work will be executed as per specification and direction of the Engineer-in-Charge.
3. The payment will be done on successful completion of work as per specification..
4. Period for the Work is 6 Week after the issue of Work Order.
5. Liquidated Damages will be deducted @0.5% of PO Value per Week for Delay.

Superintending Engineer
 AIIMS, Raipur

12/10

12/10

SCHEDULE OF QUANTITY

Name of Work: - **Supplying ,Installation,commissioning and testing of UPS System batteries at Trauma Building AIIMS Raipur.**

S.No	Description Of Items	Unit	Qty	Rate	GST %	Amount Including GST
	1 Set of 204 No's Batteries VRLA, Exide Make No-MGUP4054 or Equivalent, 165 AH, 2 Volts	Each Set	1			
	Detailed Description of items 1 Set of Batteries					
A	Supply, Installation, Commissioning and Testing of Sealed maintenance valve regulated Lead Acid (VRLA) , (Maintenance Free) batteries, Links & Cables for 100 KVA UPS system, for providing 30 minutes back up to 100 KVA UPS. Each bank of batteries shall comprise of battery: 2V x 165 AH not less than 204 nos. one set for each UPS to provide 30 minutes backup) (a) Good service life (minimum 36 months warranty) (b) Low self Discharge (c) High Reliability, Heavy duty design with superior corrosion resistant. (d) Disconnection, Physical Replacement, Connection, Testing report and satisfactory commissioning with Online UPS					
B	Freight Charges	Each Set	1			
				Total (A+B)		


Superintending Engineer
AIIMS, Raipur

Janak
12/10

12
12/16