



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
 Tatibandh, GE Road,
 Raipur-492 099 (CG)
 Phone No. 0771-2572930, e-mail: se@aiimsraipur.edu.in

NIQ No:18/EE/AIIMS/RPR/2018-19

Date: 27/02/2019

INVITING SPOT QUOTATION

Spot scaled quotation is hereby invited by The Executive Engineer (Civil) on behalf of The Director, AIIMS Raipur from the interested agencies having GSTIN/PAN No. should be submitted to office of Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to **03:00 PM** on **28th February 2019**. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at **03:30 PM**. As per detailed below:-

SCHEDULE OF QUANTITY

Name of Work: Fixing of False Ceiling and Replacement of Floor Mat with PVC Flooring in the Committee Room in Medical College, AIIMS, Raipur.

Sl No	Description of items	Unit	Quantity	Rate	Amount
1AS PER ATTACHED SHEET.....				

Conditions:

1. Item rates should be quoted inclusive of all taxes (Nothing to be paid extra on this account).
2. Work has to be done as per CPWD specification and direction of Engineer In-charge.
3. Damage if any done/happened by the Contractor has to make it good as original.
4. Security Deposit @2.5% shall be deducted & released after Defect Liability Period of 6 Months.
5. Work should be completed within 10 Days from the date of issue of work order.
6. The work may be executed day and night with the permission of competent authority to achieve the target date of completion and no any relaxation will be given anyhow.
7. Labour Law to be obeyed by the Agency.
8. Approved material will only be accepted.
9. The site is available for immediate execution of work.
10. Only those specialize agencies are advised to participate in the quotation who already done similar nature of work at urgent basis in given short duration time period.
11. An undertaking will be submitted by the successful agency to complete the work within 10 days at any cost.

Handwritten signature and date: 27/2/2019

Executive Engineer (C)
 AIIMS Raipur (Chhattisgarh)

Schedule of Quantity

Name of Work: Fixing of False ceiling and replacement of floor mat with PVC flooring in the Committee room in Medical College, AIIMS Raipur

NIQ No. - 18/EE/AIIMS/RPR/2018-19

Item No.	Description of item	Qty	Unit	Rate (Rs)		Amount (Rs)
				In Figure	In Word	
1	WOOD & P.V.C. WORK					
1.1	Providing and fixing PVC floor sheet 1.6 mm thick of approved texture and design using synthetic rubber based adhesive etc all complete as per the direction of engineer in charge.	146.00	sqm			
1.2	Providing and fixing Wall paper sheet of approved thickness, texture and design using synthetic rubber based adhesive etc all complete as per the direction of engineer in charge.	30.00	sqm			
2	ROOFING					
2.1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre,					

Schedule of Quantity

Name of Work: Fixing of False ceiling and replacement of floor mat with PVC flooring in the Committee room in Medical College, AIIMS Raipur

NIQ No. - 18/EE/AIIMS/RPR/2018-19

Item No.	Description of item	Qty	Unit	Rate (Rs)		Amount (Rs)
				In Figure	In Word	
	shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :					
2.1.1	12.5 mm thick tapered edge gypsum moisture resistant board	100.00	sqm			
3	DISMANTLING AND DEMOLISHING					

Schedule of Quantity

Name of Work: Fixing of False ceiling and replacement of floor mat with PVC flooring in the Committee room in Medical College, AIIMS Raipur

NIQ No. - 18/EE/AIIMS/RPR/2018-19

Item No.	Description of item	Qty	Unit	Rate (Rs)		Amount (Rs)
				In Figure	In Word	
3.1	Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification.					
3.1.1	Two or more coats on new work	146.00	sqm			
3.2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	100.00	sqm			
4	DISMANTLING AND DEMOLISHING					
4.1	Dismantling of spindle fire hydrant, sprinkler including stacking of useful materials within 50 metres lead.	3	each			
4.2	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing, Flooring mats and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	146.00	sqm			
Total Amount						

Seal & Signature of Contractor