



अखिल भारतीय आयुर्विज्ञानसंस्थान, रायपुर (छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
Tatibandh, GE Road,
Raipur-492 099 (CG)
www.aiimsraipur.edu.in

No. - NIQ-02/EE/AIIMS/RPR/2019-20

Date: 06-05-2019

NOTICE INVITING QUOTATION

Sealed percentage Rate quotation for the below mentioned work are hereby invited by The Executive Engineer (Civil) on behalf of The Director, AIIMS Raipur from approved and eligible Contractors/ having GSTIN/PAN no..The relevant documents should be submitted to Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to **03:00PM** on **dated: 09-05-2019**. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at **3.30PM**.

SCHEDULE OF QUANTITY

Name of Work: -- Renovation work for department of Physical Medicine and rehabilitation in, AIIMS Raipur.

| Sl. | Description of items | Unit | Qty | Rate | Amount |
|---------------------------------|----------------------|------|-----|------|--------|
|As PER SHEET ATTACHED..... | | | | | |

Conditions:

1. Percentage rate should be quoted inclusive of all the taxes (Nothing to be paid extra on this account).
2. Work shall be completed within **14 Days** from the date of issue of Work Order.
3. Work has to be done as per CPWD specification & direction of Engineer In-charge.
4. Damage if any done/happened by the contractor then, he has to make it good as original.
5. Demand Draft/FDR/bankers cheque of any scheduled Bank against **EMD Rs.1,100/-** in favour of AIIMS, Raipur which will be released after successful completion of work.
6. **Security deposit @ 2.5%** shall be deducted & released after Defect Liability Period of 6 months.
7. Labour law to be obeyed by the agency.
8. All the tax deductions if any will be done as per govt. rule.


Executive Engineer (Civil)
AIIMS Raipur


Copy To:-

1. The Director, AIIMS Raipur.
2. The Deputy Director (Admin), AIIMS Raipur.
3. Sr. Administrative Officer, AIIMS Raipur.
4. AO-1, AIIMS Raipur
5. Junior Engineer (Civil)-(Hardeep Singh Pal)- AIIMS, Raipur
6. Original Tender File -54(91)


Executive Engineer (Civil)
AIIMS Raipur

No.54 (91) SE AIIMS RPR 53
Date - 06 - 05 - 2019

o/c


06.05.19
(JAA)

SCHEDULE OF QUANTITY

AIIMS Raipur

Name of Work: Renovation Work for Department of Physical Medicine and Rehabilitation in AIIMS RAIPUR.

AIIMS Raipur

| I.No. | Description of Item | Quantity | Unit | Rate | Amount |
|-------|---|----------|-------|---------|-----------------|
| 1 | Providing and fixing in position Stainless steel Grade 304 plate-1.0 mm thick as per design for expansion joints. | | | | |
| 1.1 | 200 mm wide. | 21.00 | metre | 681.47 | 14311.00 |
| 2 | Marble stone flooring with 18 mm thick marble stone, as per sample of marble approved by Engineer-in-charge, over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry, including rubbing and polishing complete with : | | | | |
| 2.1 | Udaipur green marble | 2.00 | sqm | 1854.35 | 3709.00 |
| 3 | Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. | | | | |
| 3.1 | GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending. | 11.00 | sqm | 1215.64 | 13372.00 |
| 4 | Distempering with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. | | | | |
| 4.1 | Two or more coats on new work | 140.00 | sqm | 62.01 | 8681.00 |
| 5 | Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : | | | | |
| 5.1 | Two or more coats on new work | 150.00 | sqm | 98.53 | 14780.00 |
| | Total | | | | 54853.00 |

Percentage Quoted Rate in Figure

In word.....

(Signature of Contractor)
 Address :-
 Contact No. :-
 Email :-

Executive Engineer (Civil)
 Project Cell, AIIMS Raipur