



असतो मा सद्गमय

अखिलभारतीयआयुर्विज्ञानसंस्थान, रायपुर (छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
 Tatibandh, GE Road,
 Raipur-492 099 (CG)
 www.aiimsraipur.edu.in

NIQ No: 06/EE/AIIMS/RPR/2019-20

Date: 30-05-2019

NOTICE INVITING QUOTATION

Sealed quotation is hereby invited by The Executive Engineer (Civil) on behalf of The Director, AIIMS Raipur from intending Civil Contractors of CPWD, MES, BSNL, Chhattisgarh State PWD having relevant documents and should be submitted to office of Project Cell, Hospital Administrative Block, Gate No-01, AIIMS Raipur up to 3:00 pm on date: **03-06-2019**. The quotations will be opened on the same day at 3:30pm.

The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.

Sl No	NAME OF WORK	EST. COST in Rs.	E.M.D in Rs.	TIME
1	Providing and fixing of collapsible steel shutters at PG Intern hostel in AIIMS Raipur.	1,68,264.00	3,400.00	30days.

SCHEDULE OF QUANTITY

Sl.	Description of items	Unit	Quantity	Rate	Amount
.....As PER SHEET ATTACHED.....					

Terms & Conditions:

- The rates are to be quoted in words and figures inclusive all taxes octroi, transportation etc. (Nothing to be paid extra on this account).
- Security Deposit @2.5%** of quoted value will be deducted & will be released after **06(Six) months** of successfully completion of work.
- Liquidated damages @ 0.5%** of quoted value per week will be deducted for delay of work subject to maximum up to **10%** of quoted value.
- The work will be executed as per **CPWD specification** and direction of the Engineer-In Charge.
- The sample of all the items shall have to be got approved by the contractor from the Engineer-In-Charge/ Executive Engineer or his representative before the supply commences.
- Time period will be reckoned from the day award of the work.
- Civil item** will be taken as per mentioned make & specification on schedule of quantity (**Annexure-"A"**).
- Unless otherwise provided in the Schedule of quantities, the rates quoted by the contractor shall be all inclusive and shall apply to all heights, lifts, leads and depths of the building and nothing shall be payable to him on this account.
- The first and final bill payment will be done after completion of work as per specification.
- The bidder shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work.


11. The Contractor shall remove from site all rubbish and debris generated by the Works and keep Work site clean and tidy.
12. Self-attested copy of **Civil** Contractor registration certificate with validity, GST Registration, PAN Card should be attached with Quotation.
13. All damages done to the building during execution of **civil** work shall be the responsibility of the contractor and the same will be made good immediately at his own cost to the satisfaction of the Engineer-in-Charge. Any expenditure incurred by the department in this condition shall be recovered from the contractor and decision of the Engineer-in-Charge about recovery shall be final.
14. **EMD Rs. 3,400.00** has to be deposited in form of **DD/FDR/BG** in favor of **AIIMS Raipur** with quotation. In case the lowest bidder refuses to execute the work, EMD will be forfeited.

\

(Er. Manoj Rastogi)
Executive Engineer (Civil)
AIIMS Raipur

Copy to:

1. The Director, AIIMS Raipur.
2. DDA, AIIMS Raipur,
3. Financial Advisor, AIIMS Raipur.
4. Account Officer-I, Project Cell, AIIMS Raipur.
5. Er. Amarnath Chandra, JE (Civil) - For preparation of Analysis of rate & justification statement.
6. Original File- 54(100)


(Er. Manoj Rastogi)
Executive Engineer (Civil)
AIIMS Raipur

Schedule of Quantity				Annexure-A'	
Name of Work: Providing and fixing of collapsible steel shutters at PG Intern hostel in AIIMS Raipur.					
I.No.	Particulars	Unit	Quantity	Rate	Amount
1	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm diasteel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	Sqm	19.00	8670.50	164739.50
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
2.1	Two or more coats on new work	Sqm	29.00	121.55	3524.95
				Total	168264.00

(Rupees One Lakh Sixty-Eight Thousand Two Hundred Sixty-Four) only

Percentage Rate Quoted by the Agency (In Figures)	Above	%	Rs.
	Below	%	
Quoted Amount (In Words):Rupees			
Name of Agency:			
Address Details:			
Contact no:			
Valid email id:			

संस्कृत विश्वविद्यालय

