



No. AIIMS/R/CS/FMT/2018/02/LPC

Date: 16/03/ 2018

Inviting Quotations for “Miscellaneous Electrical Works for Laboratory Room No.3103 3rd Floor in the Department of FMT at Medical College AIIMS Raipur”.

कोटेशन सूचना
QUOTATION NOTICE

Sealed quotations are invited from approved and eligible Contractors/Firms/individuals/Supplier for “Miscellaneous Electrical Works for Laboratory Room No.3103 3rd Floor in the Department of FMT at Medical College AIIMS Raipur”. The quotation with copy of certificate of GST registration & other documents should be submitted to office of **Stores Officer, 2nd Floor Gate No-05 Medical College Building AIIMS Raipur** up to **02/04/2018** before **3:00 pm**. The quotations will be opened on the same day at **3:30pm**. As per detail given below:-

1	2	3	4	5	6	7
S.No.	ITEM DESCRIPTION	UNIT	HSN Code	QTY	UNIT PRICE IN Rs. (Including All Taxes)	Total Value
1	Supplying & Wiring for circuit/submain wiring along with earth wire with the following size of 1.1kV Grade FRLS PVC insulated copper conductor, single core multistrand cable in surface / recessed medium class PVC conduit as required.					
1A	2 X 4 sq.mm + 1 X 4 sq.mm earth wire	Meter		100	187.00	18,700.00
1B	4 X 4 sq.mm + 2 X 4 sq.mm earth wire	Meter		300	374.00	1,12,200.00
2	Supplying & Wiring for circuit/submain wiring along with earth wire with the following size of 1.1kV Grade FRLS PVC insulated copper conductor, single core multistrand cable in surface / recessed medium class ISI marked, 25mm Casing Capping as required.					
2A	2 X 4 sq.mm + 1 X 4 sq.mm earth wire	Meter		20	179.00	3,580.00
2B	4 X 4 sq.mm + 2 X 4 sq.mm earth wire	Meter		5	357.00	1,785.00

(Seal/ Signature of Contractor)

3	Supplying & Wiring for circuit/submain wiring along with earth wire with the following size of 1.1kV Grade FRLS PVC insulated copper conductor, single core multistrand cable in surface / recessed medium class as per IS standards, suitable size, metallic flexible conduit as required.					
3A	4 X 4 sq.mm + 2 X 4 sq.mm earth wire	Meter		10	495.00	4,950.00
4	Supplying & Fixing following size/modules, PVC box along with modular base & cover plate for modular switches in surface/recess etc as required.					
4A	3 Module (100mm X 75mm)	Each		10	148.00	1,480.00
4B	6 Module (200mm X 75mm)	Each		3	214.00	642.00
5	Providing and Fixing 20A/16A, 240Volt, SPN industrial type, Socket outlet with 2 pole and earth metal enclosure Plug top along with 20 /16amps C curve DP MCB in suitable sheet steel enclosure on surface or in recess with chained metal cover for the socket outlet and complete with connection, testing and commissioning as required.	Each		5	1,918.00	9,590.00
6	Supplying & Fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
6A	5/6 amps switch	Each		6	90.00	540.00
6B	15/16 amps switch	Each		10	126.00	1,260.00
6C	3 pin 5/6 amp socket outlet	Each		6	116.00	696.00
6D	6 pin 15/16 amp socket outlet	Each		10	168.00	1,680.00
7	Supplying & Fixing following way prewired TP & N MCB distribution board of steel sheet for 415Volt on surface/recess complete with loose wire box, terminal connectors for all incoming and outgoing circuits, duly prewired with suitable size FRLS PVC insulated copper bus bar , neutral link , earth bar , din bar, detachable gland plate , interconnections, powder painted including earthing etc. as required.(But without MCB/RCCB/Isolator)					
7A	12 way (4+12), Double door	Meter		1	14,283.00	14,283.00
8	Supplying & fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing & commissioning etc. as required.					

8A	Single Pole	Nos		36	203.00	7,308.00
9	Supplying & Fixing following rating four pole, 415 volts, isolator in the existing MCB DB complete with connections testing & commissioning etc as required.					
9A	63 amps	Each		1	852.00	852.00
10	Supplying & Fixing 63 Amp/4Pole/415 V/30mA-RCCB in the existing MCB DB complete with connections testing & commissioning etc. as required.	Each		1	3,245.00	3,245.00
11	Supplying & Wiring for circuit/submain wiring along with earth wire with the following size of 1.1kV Grade FRLS PVC insulated copper conductor, single core multistrand cable in surface / recessed Steel conduit as required.					
11A	4 X 25 sq.mm + 2 X 16 sq.mm earth wire	Meter		40	1,436.00	57,440.00
Total Amount (Including Taxes)						2,40,231.00

- **Firm to mention the item wise GST & HSN Code.**
- **Firm to quote the rate in above/below % of Total Amount (Including Taxes)**
=.....In Words: (_____)

नियम एवं शर्त :

Terms & Condition:

1. Percentage should be mentioned in words & figure both.
2. Taxes/GST, if any (Kindly mention, Nothing to be paid extra on this account)
3. All the material, equipment, labour and safety arrangement etc. will be arranged by the contractor. No T & P will be issued by the department.
4. Any damage done to the existing installation/building particularly due to negligence shall be entire responsibility of contractor to make good the same free of cost.
5. Work Schedule –
 - a) Firm to supply the sample for approval, within 07 days from the date of issuing of Work Order.
 - b) HOD/Incharge of concerned Department must be approved the sample physically within 07 days from the submission of sample for approval.
 - c) Firm to complete all work (Providing & fixing) within 30 days from the date of approval of physical sample.
6. No any additional documents related to this NIQ will be entertained after opening of NIQ.
7. LD @ 0.5% of delayed Providing & Fixing per week or part of week for delay of Providing & Fixing of material subject to maximum up to 10% should be deducted. After expiry of Work Schedule work cannot be accepted without extension of Work Schedule.
8. Quotation No, Name and due date of opening must be written on top of envelop.
9. Price should be FOR Destination basis. (i.e. concerned department)

(Seal/ Signature of Contractor)

10. Brand, Make should be clearly mentioned in offer (If require).
11. Item should be installed from electrical make enclosed at Annexure "B".
12. RTGS details required for payment purpose.
13. The GST registration details may please be furnished.
14. No part work or part payment will be entertained.
15. Validity of offer should not be less than 90 days.
16. Expenditure will be debitable to GIA-General.
17. The quantity in above column is totally tentative. It can be increase or decrease.
18. 100% payment against completion of work duly certified by concerned department.
19. GST rates applicable on your quoted item may please be confirmed. HSN code for each item should be clearly mentioned.
20. Please confirm if there any change (Upward/Reduction) in your Basic Price structure. And you are also requested to pass the Input Credit as per the following **Anti Profiteering Clause of GST**.
"Upon Implementation of GST, any reduction in the rate of tax on supply of goods or service or the benefit of input tax credit shall be passed on to AIIMS Raipur by way of commensurate reduction in the prices".
21. In the event of increase in price, detailed justification and supporting evidence may be submitted.
22. 10% Performance Security Deposit will be withheld from his bill and shall be released after the period of Six Month from the date of Satisfactory Completion of Work.
23. AIIMS, Raipur reserve the right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.

(Store Officer)
AIIMS, Raipur (CG)

(Seal/ Signature of Contractor)

Make of Electrical Item		
1	2	3
S.No.	ITEM DESCRIPTION	Make
1	Wiring for circuit/submain 1.1kV Grade FRLS PVC insulated copper conductor, single core multistrand cable.	HPL / KEI / HAVELLS / RR Kabel / Polycab / Finolex/ L&T or equivalent
2	Steel Conduit & Accessories	BEC, AKG, MK, NIC, Rama, Novel or equivalent
3	PVC Conduit & Accessories	AKG, MK, Anchor, Finolex, Steel Craft, Saraswati, Swastik or equivalent
4	Casing Capping	Saraswati, Polycab or equivalent
5	Modular Switch, Socket, PVC box, base & cover plate etc.	Clipsal, Crabtree, Legrand, L & T, Siemens Northwest or equivalent
6	Industrial Socket Outlets	Havells, ABB, Hager or equivalent
7	LT Panels / Feeder Pillars / Floor Panels for upto 400A i/c switchgear	L & T, ABB, Siemens, Schneider, Tricolite, Adlec, CRS, Sudhir, Jakson, Advance Panel (Narela), Adhunik, Havells, Indoasian or equivalent
8	MCCB with Thermomagnetic releases	L & T, ABB, Siemens, Schneider, GE, Legrand, Adhunik, C&S Electric or equivalent & Approved by Engineer Incharge.
9	MCCB with Variable microprocessors based releases (o/c, s/c, e/f)	L & T (D-Sine), ABB (ISO Max), Siemens, Schneider (NS Compact), GE (Recold Plus), Legrand (DPX) or equivalent & Approved by Engineer Incharge.
10	MCBs/RCCB Prewired DBs	Legrand, GE, Hager, ABB, Siemens, Schneider, Havells, or equivalent
11	Crimping lugs/thimbles	Dowells, Commet or equivalent & Approved by Engineer Incharge.
12	Cable Lugs & Gland	Dowells, Comex, Comed, Hex, Jhonson, Gripwell or equivalent & Approved by Engineer Incharge.