

No. NIA/64/ SE/AIIMS/2017-18

Date: 22/06/2017

**NOTICE INVITING SPOT QUOTATIONS**

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors/Firms/Individuals/Supplier having TIN/PAN no./relevant documents and should be submitted to office of Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to 3:00 pm on 23<sup>th</sup> June 2017. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at 3:30 pm. As per detailed below:-

SI No	NAME OF WORK	EST. COST in	E.M.D in `	TIME
1	Providing and Fixing acid/alkali resistant tiles in UG Lab of the department of Biochemistry at Medical College, AIIMS Raipur.	Rs. 1,96,104/-	Nil	5 Days

**SCHEDULE OF QUANTITY**

Sl.	Description of items	QuantityRate	Unit	Amount
.....As PER SHEET ATTACHED.....				

**Conditions:**

1. Rate should be quoted inclusive all taxes (Nothing to be paid extra on this account). Percentage / Quantum of Tax shall be mentioned.
2. F.O.R. Project Cell, Hospital Administrative Block, Gate No-01, AIIMS Raipur.
3. Six month warranty from the date of providing or as per manufacturer which is more & damages during transportation to be liable to contractor. 5% security deposit will be withheld from his bill and shall be released after the period of six month from the date of completion.
4. The supply will be taken as per mentioned make on schedule of quantity i.e. as per specification.
5. Work should be completed within 5 days from the date of issue of WO.
6. The right to reject any or all the quotations without assigning any reasons and accept full or part of Quotation thereof shall rest with undersigned.
7. Tiles to be used in the work should have make of Kajaria/Somany/Nitco.

Contd.

*[Signature]*  
22/06/17

*[Signature]*  
22/06/17


Copy to-

- 1) Director, AIIMS Raipur – For information please
- 2) Deputy Director Admin, AIIMS Raipur – Spot quotation called as discussed seeing the urgency of work
- 3) Financial Advisor, AIIMS Raipur- For information please
- 4) Sr. Administrative Officer, AIIMS Raipur - For information please
- 5) Contractors - For information please


6) AE(C), AIIMS Raipur--- } You are instructed to collect the quotation personally & submit upto  
3:00 PM on 23/06/17

7) All JE (C/E), AIIMS Raipur.

8) Notice Board

  
JE (C)  
AIIMS Raipur

  
SE  
AIIMS Raipur


  
EE(C)  
AIIMS Raipur

## SCHEDULE OF QUANTITY

**Name of Work:** Providing and Fixing acid/alkali resistant tiles in UG Lab of the department of Biochemistry at Medical College, AIIMS Raipur.

S no	DSR Ref. No.	Description of item	Qty	Unit	Rate	Amount
1	11.21	Providing and fixing 10 mm thick acid and/or alkali resistant tiles of approved make and colour using acid and/or alkali resisting mortar bedding, and joints filled with acid and/or alkali resisting cement as per IS : 4457, complete as per the direction of Engineer-in- Charge.				
	11.21.1	In flooring on a bed of 10 mm thick mortar 1:4 (1 acid proof)				
	11.21.1.1	Acid and alkali resistant tile	188	sqm		
	11.21.2	In dado/skirting on 12 mm thick mortar 1:4 (1 acid proof) cement : 4 coarse sand)				
	11.21.2.1	Acid and alkali resistant tile	8	sqm		
2	11.42	Deduct for not using 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles and jointing with grey cement slurry @ 3.3kg/sqm	188	sqm		
3	11.43	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness.	188	sqm		
4	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
	15.23.1	For thickness of tiles 10 mm to 25 mm	8	sqm		
Total Amount						

(Signature of Contractor)

  
 Executive Engineer (Civil)  
 Project Cell, AIIMS Raipur