



अखिल भारतीय आयुर्विज्ञानसंस्थान, रायपुर (छत्तीसगढ़)

All India Institute of Medical Sciences, Raipur (Chhattisgarh)

Tatibandh, GE Road,

Raipur-492 099 (CG)

www.aiimsraipur.edu.in

No. **NIA/11/ SE/AIIMS/ RPR/2017-18**

Date: **12/09/2017**

NOTICE INVITING QUOTATION

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from Contractors/Firms/Individuals having GST No, TIN/PAN no. along with Earnest Money in the form of Demand Draft or Pay Order or Banker's Cheque or Deposit at Call Receipt or Fixed Deposit Receipt of a Scheduled Bank (drawn/ Pledged in favour of AIIMS, Raipur) and shall be valid upto 60 days and should be submitted to office of Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to 3:00 pm on 19th September 2017. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at 3:30 am. As per detailed below:-

Sl No	NAME OF WORK	EST. COST in	E.M.D in	TIME
1	Construction of GI Chain Link Fencing Around Temporary Basketball Court Near STP at AIIMS Raipur	Rs. 2,69,595 /-	10000/-	01 Month

SCHEDULE OF QUANTITY

Sl.	Description of items	Unit	Qty	Rate	Amount
As PER SHEET ATTACHED.....				

Conditions:

1. Rate should be quoted inclusive of all the taxes (Nothing to be paid extra on this account). Percentage / Quantum of Tax shall be mentioned.
2. F.O.R. Project Cell, Hospital Administrative Block, Gate No-01, AIIMS Raipur.
3. The right to reject any or all the quotations without assigning any reasons and accept full or part of Quotation thereof shall rest with undersigned.
4. The supply will be taken as per mentioned make on schedule of quantity i.e. as per specification.
5. Work should be completed within 30 days from the date of issue of WO.
6. In case the agency is not started the work within 5 days of issue of the work order then the entire amount of EMD shall be forfeited by AIIMS Raipur.
7. LD @ 0.5% of WO value per week will be deducted for delay in completion of work subject to maximum up to 10% of WO value.
8. The agency has to submit invoice for all material to be utilized in the work.
9. MS sections to be used of Jindal/TATA/RINL/Sail.

JE (C)

AIIMS Raipur

SE

AIIMS Raipur

SCHEDULE OF QUANTITY

Name of Work: Construction of GI Chain Link Fencing Around Temporary Basketball Court Near STP at AIIMS Raipur

S no	DSR ref no	Description of item	Unit	Qty	Rate(in Rs..)		Amount
					In Words	In Figure	
Earth works							
1	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m: All kinds of soil:	5.00	Cum			
Dismantling and Demolishing							
2	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	0.50	Cum			
Cement Concrete							
3	4.1.4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size) :	5.00	Cum			
Steel works							
4	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1500.00	Kgs			
Finishing work							
5	13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work	51.00	Sqm			

[Signature]

Fencing wire work							
6	16.70.1	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge : Made of G.I. wire of dia 4 mm	220.00	Sqm			
						Total	

Total in words..... Total in Figure.....

(Signature of Contractor)

Superintending Engineer

Project Cell, AIIMS Raipur