



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
 Tatibandh, GE Road,
 Raipur-492 099 (CG)
www.aiimsraipur.edu.in

No. **NCG-20/SE/AIIMS/RPR/2017-18**

Date: 16/01/2018

NOTICE INVITING SPOT QUOTATION

Sealed Item Rates quotations for the below mentioned work are hereby invited by The Superintending Engineer on behalf of The Director, AIIMS Raipur from approved and eligible Contractors/Firms/Individuals/Supplier having GSTIN/PAN no./ relevant documents should be submitted to/ collected by Junior Engineers, Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to 3:00 pm on 17th January 2018. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at 3:30 pm. As per detailed below:-

SCHEDULE OF QUANTITY

Name of Work:-- Miscellaneous Painting works at AIIMS Raipur under Kayakalp

Sl.	Description of items	Unit	Qty	Rate	Amount
As PER SHEET ATTACHED.....				

Conditions:

1. Rate should be quoted inclusive of all the taxes (Nothing to be paid extra on this account). Percentage / Quantum of Tax shall be mentioned.
2. Work shall be completed within 10 (Ten) Days from the date of issue of WO.
3. Work has to be done as per CPWD specification & direction of Engineer In-charge.
4. As the work is to be done in running Hospital, the restrictions if any has to be obeyed by the Contractor.
5. Damage if any done/happened by the contractor then, he has to make it good as original.
6. Payment shall be done for the work done and measured.
7. Security deposit @ 5% shall be deducted & released after Defect Liability Period of 6 months.
8. Labour law to be obeyed by the agency.

Junior Engineer (Civil)
 AIIMS Raipur

Superintending Engineer
 AIIMS Raipur

Copy To:

1. The Director, AIIMS Raipur.
2. The Medical Superintending, AIIMS Raipur
3. The Deputy Director (Admin), AIIMS Raipur.
4. The Financial Advisor, AIIMS Raipur.
5. Sr. Administrative Officer, AIIMS Raipur.
6. M/S B.L. Kashyap
7. M/S Geeta Fabricator
8. M/S Puskar Gokulka
9. M/S First Construction
10. Er. Nayan Parakh, JE(C)
11. Er. Parag Yadu, JE(C)

For Information

For Information & Necessary actions

You are instructed to collect as many quotation personally so that competitive rates may be recorded

Superintending Engineer
 AIIMS Raipur

Schedule of Quantity


Name of Work: Miscellaneous Painting works at AIIMS Raipur under Kayakalp

S no	DSR ref no	Description of item	Qty	Unit	Rate		Amount
					(In Figures)	(In Words)	
1	13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :					
1.1	13.61.1	Two or more coats on new work	1080.0	Sqm			
2	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	90.0	Sqm			
3	13.83	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.					
3.1	13.83.1	One coat	470.0	Sqm			
4	14.64	Finishing walls with water proofing cement paint of required shade :					
4.1	14.64.2	Old work (one or more coats @ 2.20 kg/10 sqm) complete.	315.0	Sqm			
5	14.66	Finishing walls with Acrylic Smooth exterior paint of required shade:					
5.1	14.66.2	Old work (One or more coat applied @ 0.90 ltr/10 sqm).	315.0	Sqm			
6	14.75	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	5.0	Sqm			
Total							

Total in words.....

Total in Figure.....

(Signature of Contractor)


 Superintending Engineer
 Project Cell, AIIMS Raipur