

No. NIQ-02(2<sup>nd</sup> Call)/SE/ AIIMS/RPR/2018-19Date: 16<sup>th</sup> April 2018**NOTICE INVITING QUOTATION****2<sup>nd</sup> Call**

Sealed Item Rates quotations for the below mentioned work are hereby invited by The Superintending Engineer on behalf of The Director, AIIMS Raipur from approved and eligible Contractors/Firms/Individuals/Supplier having GST/TIN/PAN no./relevant documents along with Earnest Money in the form of Demand Draft or Pay Order or Banker's Cheque or Deposit at Call Receipt or Fixed Deposit Receipt of a Scheduled Bank (drawn/ Pledged in favour of AIIMS, Raipur) and should be submitted to office of Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to 03:00 PM on 23<sup>rd</sup> April 2018. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at 3:30 pm. As per detailed below:-

S No	NAME OF WORK	E.M.D in Rupees	Time
1	Providing and fixing of grill at balconies of type 2B quarters at ground floor at AIIMS Residential Complex.	Rs.2000	45 days

**SCHEDULE OF QUANTITY**

Sl.	Description of items	Unit	Qty	Rate	Amount
.....As PER SHEET ATTACHED.....					

**Conditions:**

- Rate should be quoted inclusive of all the taxes (Nothing to be paid extra on this account). Percentage / Quantum of Tax shall be mentioned.
- All the relevant documents to be submitted must be sealed and signed by the proprietor/contractor/authorised signatory of the firm.
- The Schedule of Quantity must be filled with blue ball point pen and contractor must seal and sign on every page.
- The rights to reject any or all the quotations without assigning any reasons and to accept full or part of Quotation thereof shall rest with Superintending Engineer, AIIMS Raipur.
- Work should be completed within 45 Days from the date of issue of WO.
- All works shall be carried out as per CPWD specifications and directions of Engineer In-charge.
- In case the agency does not start the work within 15 days from the date of acceptance of work order, entire EMD will be forfeited by AIIMS Raipur.
- As the work is to be done in occupied residences, the restrictions if any have to be obeyed by the Contractor.
- Damage if any caused by the agency or his workmen will render the contractor liable for making the damaged property good as original.
- Security deposit @ 5% shall be deducted from all RA bills & released after Defect Liability Period of 6 months.
- Labour law to be obeyed by the agency.
- The man power engaged in the work should be covered with insurance which will be the responsibility of the Agency.
- The agency has to follow the all PF & ESI compliances.

Junior Engineer (Civil)  
AIIMS Raipur

Superintending Engineer  
AIIMS Raipur

**Schedule of Quantity**

AIIMS Raipur

Name of Work: Providing and fixing of grill at balconies of type 2B quarters at ground floor at AIIMS Residential Complex.

**SUB HEAD 1: Brickwork**

Sno.	DSR Reference	Item	Qty	Unit	Rate		Amount
					In Figures	In Words	
1.1	6.32	Brick work with clay fly ash F.P.S. (non modular) brick of class designation 7.5 in superstructure above plinth level up to floor five level in :					
1.1	6.32.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	1.5	cum			

**SUB HEAD 2: FINISING**

2.1	13.1	12 mm cement plaster of mix :					
2.1.1	13.1.2	1:6 (1 cement: 6 fine sand)	7.6	sqm			
2.2	13.2	15 mm cement plaster on the rough side of single or half brick wall of mix :					
2.2.1	13.2.2	1:6 (1 cement: 6 fine sand)	6.2	sqm			
2.3	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	7.6	sqm			
2.4	13.45	Finishing walls with textured exterior paint of required shade :					
2.4.1	13.45.1	New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm	6.2	sqm			
2.5	13.42	Distempering with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification.					
2.5.1	13.42.1	Two or more coats on new work	7.6	sqm			
2.6	13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :					
2.6.1	13.61.1	Two or more coats on new work	29	sqm			

**SUB HEAD 3: DISMANTLING AND DEMOLISHING**

3.1	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	5.5	sqm			AIIMS Raipur
3.2	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.					
3.2.1	15.23.1	For thickness of tiles 10 mm to 25 mm	1.8	sqm			

**SUB HEAD 4: CONCRETE WORK**

4.1	4.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing :					
4.1.1	4.2.3	1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	0.3	Cum			

**SUB HEAD 5: WOOD & P.V.C. WORK**

5.1	9.48	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.					
5.1.1	9.48.2	Fixed to openings / wooden frames with rawl plugs screws etc.	552	kg			
		<b>Total In Figures</b>					
		<b>Total in Words</b>					

Contractor's Signature



Superintending Engineer  
AIIMS Raipur