



No. NIA-06/EE/AIIMS/RPR/2018-19

Date: 31/10/2018

**NOTICE INVITING QUOTATION**

Sealed percentage Rate quotation for the below mentioned work are hereby invited by The Executive Engineer (Civil) on behalf of The Director, AIIMS Raipur from approved and eligible Contractors/Firms/Individuals/Supplier having GSTIN/PAN no./ relevant documents should be submitted to Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to **3:00 pm** on **12<sup>th</sup> November 2018**. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at **3:30 pm**.

**SCHEDULE OF QUANTITY**

Name of Work: -- Development of Sports Ground in the campus of residential Complex, AIIMS, Kabir Nagar, Raipur.

Sl.	Description of items	Unit	Qty	Rate	Amount
.....As PER SHEET ATTACHED.....					

**Conditions:**

1. Percentage rate should be quoted inclusive of all the taxes (Nothing to be paid extra on this account).
2. Work shall be completed within **15 Days** from the date of issue of Work Order.
3. Work has to be done as per CPWD specification & direction of Engineer In-charge.
4. Damage if any done/happened by the contractor then, he has to make it good as original.
5. Security deposit @ 2.5% shall be deducted & released after Defect Liability Period of 6 months.
6. Labour law to be obeyed by the agency.

  
Executive Engineer (Civil)  
AIIMS Raipur

**Copy To:-**

1. The Director, AIIMS Raipur.
2. The Deputy Director (Admin), AIIMS Raipur.
3. Sr. Administrative Officer, AIIMS Raipur.
4. AO-1, AIIMS Raipur
5. Junior Engineer (Civil), AIIMS, Raipur

  
Executive Engineer (Civil)  
AIIMS Raipur

## Schedule of Quantities

AIIMS Raipur

**Name of work** - Development of sports Ground in the campus of residential complex,  
AIIMS, Kabir Nagar, Raipur

**Sub Head**- Jungle cleaning, levelling of ground.

I.No.	Particulars	Unit	Quantity	Rate	Amount
	<b>SUB HEAD I : EARTHWORK</b>				
1.1	Rolling with power roller of minimum 8 tones for banking excavated earth in layers not exceeding 20 cm in depth.	Cum	1770.00	3.21	5681.70
1.2	Surface dressing and leveling of the ground in required slope including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m.				
1.2.1	All kinds of soil	Sqm	8850.00	16.28	144078.00
1.3	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqm	8850.00	8.40	74340.00
	<b>TOTAL</b>				<b>224099.70</b>

Percentage Quoted Rate in Figure

.....

....

In word.....

.....

....

(Signature of Contractor)  
(Civil)

Executive Engineer  
Project Cell, AIIMS Raipur