



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)  
**All India Institute of Medical Sciences, Raipur (Chhattisgarh)**  
Tatibandh, GE Road,  
Raipur-492 099 (CG)  
[www.aiimsraipur.edu.in](http://www.aiimsraipur.edu.in)

NIQ No. 11/EE/AIIMS/RPR/2018-19

Date: 20/11/2018

**SPOT QUOTATION**

**"Kayakalp"**

Sealed Item Rate Quotations are hereby invited by The Executive Engineer (Civil) on behalf of The Director, AIIMS Raipur from the interested agencies having GSTIN, PAN No. and other relevant documents should be submitted to Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to **03:00 pm on 25<sup>th</sup> November, 2018**. Schedule of Quantity will be issued to the applicant from this office to eligible specialised agencies, who has appropriate work experience in the respective fields. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.

**SCHEDULE OF QUANTITY**

**Name of Work: Renovation of 33 KV substation at AIIMS Campus, Raipur**

S.No.	Description of items	Unit	Qty.	Rate		Amount
				In figures	In words	
1.	Supply and application of red oxide paint, aluminium paint on existing MS H beam channel and rail pole	Job	01			
2.	Supply and Erection and alignment of 33 KV isolator 800 AMP isolators without erath switch complete with all.	Set	05			
3.	Supply and erection of 33 KV LA (Light arrestor) complete with all accessories.	Job	06			
<b>Grand Total</b>						

o/c

**Name of Work:** Chemical water proofing treatment of AHU Rooms for Modular Operation Theatre at A-A1, & B-B1 in Hospital Complex, AIIMS Raipur.

S. No.	Description of items	Unit	Qty.	Rate		Amount
				In figures	In words	
1.	Cleaning washing and treating the cracks, voids if any by applying SBR based Multipurpose Polymer for water Proofing and Repair Sika Latex power or equivalent (one coat) Bond Coat. Then applying two component acrylic cementitious waterproofing, coating system (two coats) of Sika Topseal 107 or Equailent. Complete as per manufacture's specification & as per direction of the Engineer-in-charge i.e. all scaffolding and all lifts etc. complte. The treatment should be of to 10 year guarantee (10% amount will be retained for 10 years in which 5% will be released after 5 years and remaining after 5 years.	SQM.	1218.00			
2.	sealing the craccks/Joint , filling one part Elastic adhesive/sealant Sika Sikaflex Construction (Ap) or Equivalent applying self adhesive bituminous sealing tape Sika Multiseal or Equalent over the Sika Flex construction (Ap) or Equailent. Complete as per manufacture's specification & as per direction of the Engineer-in Charge. Including in all scaffoldings all lifts. The payment will be made once irrespective of duration of scaffolding.	Mt.	108.00			
<b>Grand Total</b>						


**Conditions:**

1. Item rate should be quoted inclusive of all the taxes (Nothing to be paid extra on this account).
2. Work shall be completed **within 15 days** from the date of issue of work order.
3. Work has to be done as per CPWD specification & direction of Engineer In-charge.
4. Damage if any done/happened by the contractor then, he has to make it good as original.
5. Security deposit @ 2.5% shall be deducted & released after Defect Liability Period of 6 months.
6. Labour law to be obeyed by the agency.
7. Approved material will only be accepted.

  
Executive Engineer (Civil)  
AIIMS, Raipur

**Copy To:-**

1. The Director, AIIMS, Raipur for information please.
2. The Deputy Director (Admin), AIIMS Raipur for information please.
3. Sr. Administrative Officer, AIIMS Raipur for information please.
4. AO-1, AIIMS Raipur for information please.
5. Junior Engineer (Civil), AIIMS, Raipur.
6. Junior Engineer (Electrical), AIIMS, Raipur.

  
Executive Engineer (Civil)  
AIIMS Raipur

