



अखिल भारतीय आयुर्विज्ञानसंस्थान, रायपुर (छत्तीसगढ़)

**All India Institute of Medical Sciences, Raipur (Chhattisgarh)**

Tatibandh, GE Road,

Raipur-492 099 (CG)

[www.aiimsraipur.edu.in](http://www.aiimsraipur.edu.in)

No. NIQ-14/EE/AIIMS/RPR/2018-19

Date: 06/12/2018

**SPOT QUOTATION**

Sealed percentage Rate quotation for the below mentioned work are hereby invited by The Executive Engineer (Civil) on behalf of The Director, AIIMS Raipur from approved and eligible Contractors/Firms/Individuals/Supplier having GSTIN/PAN no./ relevant documents should be submitted to Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to **3:00 pm on 06<sup>th</sup> December 2018**. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at **3:30 pm**.

**SCHEDULE OF QUANTITY**

**Name of Work: -- Providing and Fixing of Electrical conduit, Raceway/Cable tray for cabling of Audio- Visual system and stage lighting work in Auditorium, AIIMS Raipur.**

Sl.	Description of items	Unit	Qty	Rate	Amount
.....As PER SHEET ATTACHED.....					

**Conditions:**

1. Percentage rate should be quoted inclusive of all the taxes (Nothing to be paid extra on this account).
2. Work shall be completed within **15 Days** from the date of issue of Work Order.
3. Work has to be done as per CPWD specification & direction of Engineer In-charge.
4. Damage if any done/happened by the contractor then, he has to make it good as original.
5. Security deposit @ 2.5% shall be deducted & released after Defect Liability Period of 6 months.
6. Labour law to be obeyed by the agency.

  
Executive Engineer (Civil)  
AIIMS Raipur

**Copy To:-**

1. The Director, AIIMS Raipur.
2. The Deputy Director (Admin), AIIMS Raipur.
3. Sr. Administrative Officer, AIIMS Raipur.
4. AO-1, AIIMS Raipur
5. Junior Engineer (Electrical), AIIMS, Raipur

  
Executive Engineer (Civil)  
AIIMS Raipur

## Schedule of Quantities

**Name of Work:** Providing and Fixing of Electrical conduit, Raceway/Cable tray for cabling of Audio- Visual system and stage lighting work in Auditorium, AIIMS Raipur

S.N.	DSR no.	Description	Unit	Qty	Rate	Amount
1	4.6	Supplying and installing following size of perforated Hot Dipped Galvanized Iron cable tray (Galvanization thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required.				
	4.6.1	100 mm width X 50 mm depth X 1.6 mm thickness	meter	15	599.00	8985.00
	4.6.3	225 mm width X 50 mm depth X 1.6 mm thickness	meter	30	811.00	24330.00
2	4.7	Supplying and installing following size of perforated Hot Dipped Galvanized Iron cable tray "Bends" (Galvanization thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required.				
	4.7.1	100 mm width X 50 mm depth X 1.6 mm thickness	Each	2	1063.00	2126.00
	4.7.3	225 mm width X 50 mm depth X 1.6 mm thickness	Each	2	1565.00	3130.00
3	N.D.S.R.	Providing and fixing of 8 Module GI box as a gang box	Each	25	183.65	4591.25
4	N.D.S.R.	Supplying and fixing of following sizes of heavy duty PVC conduit along with accessories and GI wire (to draw and extract cable) in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.				
	(a)	25mm	meter	80	96.23	7698.40
	(b)	50mm	meter	1530	178.60	273258.00
					Total	324118.65
					<b>Say</b>	<b>324119.00</b>

Percentage Quoted Rate in Figure

.....


....

In word.....

.....

....

(Signature of Contractor)

  
 Executive Engineer (Civil)  
 Project Cell, AIIMS Raipur