



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)  
All India Institute of Medical Sciences, Raipur (Chhattisgarh)  
Tatibandh, GE Road,  
Raipur-492 099 (CG)

Phone No. 0771-2572930, e-mail: ee.civil@aiimsraipur.edu.in

NIQ No: 14/EE/AIIMS/RPR/2019-20

Date: 26-09-2019

### NOTICE INVITING QUOTATION

Sealed **percentage rate quotation** is hereby invited by The Executive Engineer (Civil) on behalf of The Director, AIIMS Raipur from the **eligible Contractors of CPWD, MES, BSNL, Chhattisgarh State PWD** having relevant documents and bid should be submitted to office of Project Cell, Hospital Administrative Block, Gate No-1, AIIMS Raipur up to **03:00PM** on 30-09-2019. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotations will be opened on the same day at **03:30 PM**. As per detailed below:

SI No	NAME OF WORK	EST. COST in Rs.	E.M.D in Rs.	TIME
1	Repair of False ceiling at Medical College Building, AIIMS Raipur.	Rs.5,94,287.00	Rs.11,900.00	15 days

### SCHEDULE OF QUANTITY

SI No	Description of items	Quantity	Unit	Rate	Amount
1	.....AS PER ATTACHED SHEET.....				

### **Conditions:**

1. The **percentage rates** are to be quoted in words and figures inclusive all taxes octroi, transportation etc. (Nothing to be paid extra on this account).
2. EMD **Rs. 11,900.00** has to be deposited in form of **DD/FDR/BG** in favor of **AIIMS Raipur** with quotation. In case the lowest bidder refuses to execute the work, EMD will be forfeited. EMD will be retained of successful bidder and will be released after successful completion of work.
3. **Security Deposit @2.5%** of quoted value will be deducted & will be released after 06(Six) months of successfully completion of work.
4. Specifications to be followed for execution of work as per CPWD Specifications-2019 and direction of the Engineer-In Charge.
5. The **first and final bill** payment will be done after completion of work as per specification.
6. Labour Law to be obeyed by the Agency.
7. **Certificate of Registration for GST, Contractors' registration & Copy of PAN card** should be attached with Quotation and duly seal & sign on each documents.
8. Time allowed for the completion of the work is **15 days**. It will be reckoned from the day award of the work.
9. The bidder shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work.

10. The Contractor shall remove from site all rubbish and debris generated by the Works and keep Works clean and tidy.
11. All damages done to the building during execution of work shall be the responsibility of the contractor and the same will be made good immediately at his own cost to the satisfaction of the Engineer-in-Charge. Any expenditure incurred by the department in this condition shall be recovered from the contractor and decision of the Engineer-in-Charge about recovery shall be final.
12. Bidders are suggested to visit the site with Junior Engineer(C) Er. Kranti Dewangan before participating in the quotation.
13. The work will be done in a running hospital, hence the work to be done as per the rules and instructions of Engineer-In-Charge. All the conditions of work at site are applicable to the successful bidder.
14. **Signing of Application/ bid:**
  - a) If the bidder is an individual, the application/bid shall be signed by him above his full type written name and current address.
  - b) If the bidder is a proprietary firm, the application/bid shall be signed by the proprietor above his full type written name and the full name of his firm with its current address.
  - c) If the bidder is a firm in partnership, the application/bid shall be signed by all the partners of the firm above their full type written names and current addresses, or, alternatively, by a partner holding power of attorney for the firm. In the later case a certified copy of the power of attorney should accompany the application. In both cases a certified copy of the partnership deed and current address of all the partners of the firm should accompany the application.
  - d) If the bidder is a limited company or a corporation, the application/bid shall be signed by a duly authorized person holding power of attorney for signing the application accompanied by a copy of the power of attorney. The bidder should also furnish a copy of the Memorandum of Articles of Association duly attested by a Public Notary.

  
 Executive Engineer (C)  
 AIIMS Raipur (C.G.)

**Copy to:**

- |  |                             |
|--|-----------------------------|
| 1. The Director, AIIMS Raipur-   | for kind information please |
| 2. The Deputy Director (Admin), AIIMS Raipur -                                 | for kind information please |
| 3. The Senior Administrative Officer, AIIMS Raipur-                            | for kind information please |
| 4. The Accounts Officer-I, Project Cell, AIIMS Raipur-                         | for information.            |
| 5. The Junior Engineer (C)-Er. Kranti Dewangan, AIIMS Raipur. -                | Preparation of Market       |
| Rate Justification, Rate analysis and measurement sheet before opening of NIQ. |                             |

### Schedule of Quantity

Name of Work: Repair of False ceiling at Medical College Building, AIIMS Raipur.

Item No	Description of item	Qty	Unit	Rate	Amount
1	<b>SUB HEAD I - ROOFING</b>				
1.1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I.				
	wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :				
1.1.1	8 mm thick calcium silicate water proof board	198.00	Sqm	1329.66	263272.68

Item No	Description of item	Qty	Unit	Rate	Amount
1.2	Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main 'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated				
	steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calicum silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening"for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I.slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all Tsections shall be pre-painted with polyster baked paint, for all heights, as per specifications, drawings and as directed by Engineer-in-Charge. <b>Note :-</b> Only calcium silicate false ceiling area will be measuredfrom wall to wall. No deduction shall be made for exposed frames/ opening (cut outs) having area less than 0.30 sqm.The calcium silicate ceiling tile shall have NRC value of 0.50 (Minimum), light reflection > 85%, non- combustible as per B.S. 476 part IV, 100% humidity resistance and also having thermal conductivity <0.043 w/ mK.	161.89	sqm	1643.95	266139.07
2	<b>SUB HEAD II - Finishing</b>				
2.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
2.1.1	Two or more coats on new work	106.00	sqm	121.55	12884.30
2.2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	228.00	sqm	115.15	26254.20

Item No	Description of item	Qty	Unit	Rate	Amount
2.3	Distemping with 1st quality acrylic distemper, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.				
2.3.1	One coat	198.00	sqm	50.60	10018.80
2.4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.				
2.4.1	Two coats	138.00	sqm	113.90	15718.20
Total					594287.25
Say					594287.00
(Rupees Five Lacs Ninety Four Thousand Two Hundred Eighty Seven Only)					
Percentage Rate Quoted by the Agency	In Figure				
	In Words				
Name of Agency:					
Address Details:					
Contact no:					
Valid email id:					

