



NIQ No: 44/EE/AIIMS/RPR/2019-20

Date: 22-01-2020

NOTICE INVITING QUOTATION

Sealed Percentage Rate quotation for the below mentioned work is hereby invited by The Executive Engineer (Civil) on behalf of The Director, AIIMS Raipur from approved and eligible Contractors/having GST Registration Certificate. The relevant documents should be submitted to Project Cell, Hospital Administrative Block, Gate No-01, AIIMS Raipur up to 12:00 noon on 24-01-2020. The quotations will be opened on the same day at 12:30pm. As per detailed below:-

The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.


Sl No	NAME OF WORK	EST. COST in `	TIME
1	Painting of Room and Repair of False Ceiling in Hospital Block, AIIMS Raipur	Rs. 28,251.00	07 days.

SCHEDULE OF QUANTITY

Sl.	Description of items	Quantity	Unit	Rate	Amount
.....As PER SHEET ATTACHED.....					

Terms & Conditions:

1. The percentage rates are to be quoted in words and figures inclusive all taxes octroi, transportation etc. (Nothing to be paid extra on this account).
2. The work will be executed as per CPWD specification and direction of the Engineer-In Charge.
3. Time allowed for the completion of the work is **07 days**. It will be reckoned from the day award of the work.
4. The first and final bill payment will be done after completion of work as per specification.
5. All damages done to the building during execution of work shall be the responsibility of the contractor and the same will be made good immediately at his own cost to the satisfaction of the Engineer in Charge. Any expenditure incurred by the department in this condition shall be recovered from the contractor and decision of the Engineer-in-Charge about recovery shall be final.
6. Labour law to be obeyed by the agency.


(Er. Manoj Rastogi)
Executive Engineer (Civil)
AIIMS Raipur

Copy to:

1. The Director, AIIMS Raipur.
2. DDA, AIIMS Raipur,
3. Financial Advisor, AIIMS Raipur.
4. Account Officer-I, Project Cell, AIIMS Raipur- Please process the quotation when put up and to be decided same day of opening only.
5. The Junior Engineer (C)-Er. Hardeep Singh Pal, AIIMS Raipur. - Preparation of Market Rate Justification, Rate analysis and measurement sheet before opening of NIQ.

(Er. Manoj Rastogi)
Executive Engineer (Civil)
AIIMS Raipur



SCHEDULE OF QUANTITY

Name of Work: Painting of Room and Repair of False Ceiling in Hospital Block, AIIMS Raipur

I.NO	Description of Item	Qty	Unit	Rate	Amount
1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :				
1.1	12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) : 2011 (Board with BIS certification marks)	9.00	sqm	1117.65	10058.85
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	12.00	sqm	115.15	1381.80
3	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.				
3.1	Two coats	46.00	sqm	81.90	3767.40
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.				
4.1	Two coats	111.00	sqm	113.90	12642.90
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
5.1	One or more coats on old work	5.00	sqm	79.95	399.75
	Total				28250.70
	Grand Total				28250.70
	Say				28251.00
Percentage Rate Quoted by the Agency		In Figure			
		In Words			
Name of Agency:					
Address Details:					
Contact no:					
Valid email id:					

