अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर(छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
Tatibandh, GE Road, Raipur-492 099 (CG)
www.aiimsraipur.edu.in

No.: E-21820/SE/AIIMS RAIPUR/2025-26/LPC/11 **Date**: 04/11/2026

QUOTATION NOTICE (5th call)

Inviting quotations for the "Detection and Rectification of Faults in Underground Power Cables, including Restoration Works, at AIIMS Raipur".

Sealed quotations are invited from eligible enlisted contractor of CPWD / M.E.S. / BSNL (Construction) / Railway / C.G.P.W.D. having Valid Electrical license for "Detection and Rectification of Faults in Underground Power Cables, including Restoration Works" at AIIMS Raipur and should be submitted to office of the Superintending Engineer, 2nd Floor, A-Block, Administrative Building, Gate no.-5, Tatibandh, AIIMS, Raipur up to 3:00 pm on 10.11.2026 item description as per detailed below:

Sr No	Description of item	Unit	Qty	Rate	GST amount	Amount
1	Supplying and making straight through cable jointing with cast resin compound, including ferrule and other jointing materials, for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required.					
1.1	300 sq. mm	Each	2.00			
2	Supplying and making indoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required.					
2.1	300 sq. mm	Each	2.00			
3	Providing services for detection and tracing of fault in 11 kV, 3-core HT underground cable (approx. 500 metres) laid at 1.2–1.5 metres depth below ground, using suitable fault locating equipment.	Job	1.00			
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.					
	All kinds of soil	cum	8.00			
				Total		
In words:						

PTO

Terms & Conditions: -

1. Rate should be mentioned in words & figure both.
2. Taxes, if any (should be clearly mention).
3. Work should be completed within 30 days from the date of issue of Work Order.
4. Price should be FOR Destination basis.
5. LD @ 0.5% of delayed completion per week or part of week for delayed work completed, subject to maximum up to 10%.
6. Quotation No/Name and Due date of opening must be written on cover top of the envelope.
7. GST rates applicable on your quoted item may please be confirmed.
8. 100% payment against final completion of work & satisfaction of Engineer-In-Charge.
9. Lowest Price L1 will be decided on total amount basis.
10. The GST registration details may please be furnished.
11. Validity of offer should not be less than 90 days
12. Part Payment will not be entertained.
13. RTGS detail required for payment purpose.
14. Expenditure will be debitable to GIA-general.
15. The bidder shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, facilities for workers and all other services required for executing the work.
16. All damages done to the building during execution of work shall be the responsibility of the contractor and the same will be made good immediately at his own cost to the satisfaction of the Engineer-in-Charge. Any expenditure incurred by the department in this condition shall be recovered from the contractor and decision of the Engineer-in-Charge about recovery shall be final.
17. Bidders are suggested to visit the site before participating in the online e-quotation.
18. The work will be done in a running hospital, hence the work to be done as per the rules and instructions of Engineer-In-Charge. All the conditions of work at site are applicable to the successful bidder.
19. All materials required for the job will have to be arranged by the Firm meeting the relevant codes specifications.
20. The Firm will have to make his own arrangement to transport the required materials shifting inside AIIMS and leaving the premises in a neat and tidy condition after the completion of the job to the satisfaction of the Engineer In charge.
21. The Firm will have to arrange for safe keeping of his materials and should provide necessary security arrangements for safe guarding the materials.
22. The Firms should note the site conditions before quoting, for the execution of this job and it will be sole responsibility of the firm to ensure that they abide by the various rules.
23. AIIMS Raipur reserves the right to place the order for full or part quantity to one or more items.

Sd/-
Superintending Engineer (offg.)
AIIMS Raipur (C.G.)